

BILANS ROBÓT ZIEMNYCH – ciąg pieszo-rowerowy							
Pikietą	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Catk. obj. wykopu	Catk. obj. nasypu	Obj. netto
9+888.7	0.0	1.2	0.0	0.00	0.00	0.00	0.00
9+900.0	0.0	1.9	0.1	17.24	0.06	17.24	-17.18
9+950.5	0.0	2.0	0.0	99.29	0.06	116.53	-116.47
10+000.3	0.0	1.3	0.1	84.21	0.17	200.74	-200.57
10+050.1	0.0	3.4	0.1	118.46	0.29	319.20	-318.91
10+100.9	0.1	3.6	1.5	177.66	1.74	496.87	-495.12
10+153.3	0.0	2.3	1.7	155.53	3.48	652.39	-648.91
10+201.1	0.0	2.3	0.2	109.52	3.68	761.91	-758.23
10+251.1	0.0	2.7	0.0	123.28	3.68	885.19	-881.51
10+301.7	0.0	0.9	0.6	89.74	4.26	974.93	-970.67
10+350.1	0.0	1.5	0.6	56.27	4.81	1031.19	-1026.38
10+401.1	0.0	2.3	0.0	95.37	4.81	1126.56	-1121.75
10+451.2	0.0	1.3	0.1	90.31	4.91	1216.87	-1211.96
10+501.1	0.0	2.2	0.1	88.63	5.00	1305.50	-1300.50
10+551.1	0.0	2.8	0.0	126.65	5.00	1432.15	-1427.15
10+601.1	0.0	3.7	0.0	162.55	5.00	1594.70	-1589.70
10+651.3	0.0	2.8	0.0	162.32	5.00	1757.02	-1752.01
10+701.3	0.0	1.4	0.0	104.66	5.01	1861.68	-1856.67
10+751.6	0.0	2.0	0.0	84.68	5.03	1946.36	-1941.33
10+801.3	0.0	2.2	0.0	105.06	5.03	2051.42	-2046.40
10+851.6	0.0	1.6	0.0	96.43	5.03	2147.85	-2142.83
10+901.6	0.0	2.4	0.0	99.52	5.03	2247.37	-2242.34
10+951.1	0.0	2.2	0.0	114.71	5.03	2362.08	-2357.05
11+001.4	0.0	3.8	0.0	152.13	5.03	2514.21	-2509.18
11+051.3	0.0	3.9	0.0	192.88	5.03	2707.09	-2702.06
11+101.3	0.0	3.2	0.0	177.97	5.03	2885.06	-2880.03
11+151.3	0.0	2.9	0.0	153.28	5.03	3038.34	-3033.31
11+201.3	0.0	2.5	0.0	135.75	5.03	3174.09	-3169.06
11+251.3	0.0	2.5	0.0	124.44	5.03	3298.53	-3293.50
11+301.3	0.0	0.6	0.6	78.28	5.62	3376.81	-3371.19
11+351.2	0.0	2.7	0.6	84.17	6.20	3460.97	-3454.77
11+401.2	0.0	2.8	0.0	137.83	6.20	3598.81	-3592.60
11+451.2	0.0	1.6	0.0	108.84	6.21	3707.64	-3701.44
11+501.7	0.0	2.6	0.0	106.17	6.21	3813.81	-3807.60
11+551.4	0.0	3.5	0.0	152.13	6.22	3965.94	-3959.72
11+574.7	0.0	3.3	0.0	79.11	6.22	4045.05	-4038.84

Tab. 3 - Tabela robót ziemnych